

City of Iron River

Where You are Always Home!

**106 W. Genesee Street
Iron River, Michigan 49935**

David A. Thayer
City Manager
citymanager@ironriver.org

Phone: 906-265-4719
Fax: 906-265-5776
Web Page: www.ironriver.org

Welcome Signs Landscaping Project
Request for Proposal/Bid
May 7, 2019

The City recently installed three Welcome Signs at the city limits along the three entryways into the city. Now the signs needed landscaping to finish the installation project. The following are features we are looking to incorporate into the design:

1. Build a 6' x 12' frame of 6" x 6" timbers with 60% pressurized treatment level. The low end will be two tiers high dolled together. The frame does not have to be completely level. The bottom tier along the low side could be cut in half at a 45-degree angle and the high side countersunk slightly to help create a level top tier. The 6' end will abut the white posts with 18" before the sign, 6" at the post, and 4' behind the sign.
 2. Remove the existing sod within the frame and backfill with sand to the bottom of the top tier.
 3. Place fabric cloth over the sand, then fill with 5"- 6" of white quartz stone. (Source is from the Felch mine.)
 4. Plant two 3'- 4' Blue-Green Juniper trees along the backside of the sign evenly spaced.
- A. M-189 sign is 12' and ½" wide. The left side is 40" tall and the right side is 54" tall from the bottom of the sign to the ground.
- B. W US 2 sign is 12' and ¼" wide. The left side is 50" tall and the right side is 40" tall from the bottom of the sign to the ground. There is a medium falloff on the backside of the sign.
- C. E US 2 sign is 12' and ½" wide. The left side is 44 ½" tall and the right side is 45" tall from the bottom of the sign to the ground. There is a sharp falloff in front of the sign.

Please return your proposal/bid to my office at the above listed address by Friday, May 17, 2019 at 2:00 p.m. The City reserves the right to reject any and all bids. The selected contractor shall be appropriately insured and licensed. The project shall be completed by June 21, 2019 unless otherwise agreed to by the City. If you have any questions, please contact me.

David A. Thayer
City Manager